

EDDS 2014 - SUMMARY OF PROPOSED CHANGES - as of April 7, 2014

| EDDS # | Requested Change | Why? | Location in EDDS |
|---------|--|---|---|
| 2014-1 | Change the Reclaimed Water definition in EDDS 2.020. | To be consistent with OMC 13.24.020. | 2.02 |
| 2014-2 | Restucture Chapter 2 contents to combine transportation elements; move Franchise Utilities (2.040C) to its own section, 2.060 - Make necessary changes to chapter contents. | Clarity | 2.040 to 2.070 |
| 2014-3 | Insert reference to Olympia GSP section 1-05.4 in EDDS 3.010, and change the relevant subsections in EDDS chapters regarding surveying and staking. | Ensure consistent wording for surveying and staking requirements in the relevant chapter subsections. | 3.010, 6.150, 7A.030, 5.030 4B.190 |
| 2014-4 | Revise sewer main Utility Extension requirements | For consistency with approved Wastewater Plan | 3.110C |
| 2014-5 | Bike Facilities: a. Update Bikeway Classes in drawings b. Table 2 - change text to refer to exceptions, not map c. Table 3 - Change Bicycle Facilities text in table d. 4D.020 - List of exceptions to bicycle facilities e. Appendix - Remove bike map (replace w/list of exceptions to policy) f. Drawings 4-2A-D - Remove class III option from major street cross sections | BPAC approved changes | Chapter 4, including applicable drawings |
| 2014-6 | Remove HPS streetlight references, add LED; remove/revise Table 14 - remove table references and text as necessary | Consistent with council direction | 4F.020, Table 14 |
| 2014-7 | Alleys and commercial access - change language to be consistent with Ordinance 6195 passed in 2002 | Consistency with Ordinance | 4I.080 |
| 2014-8 | Change 6" thickness of concrete driveway approaches to 9" | Standard is 9", but some drawings still indicate 6" | drawings 4-7A,7B |
| 2014-9 | Add suggested reference to drawing 5-12 in Section 5.28 | Clarity | 5.028 Solid Round Catch Basin Covers |
| 2014-10 | Add note to Catch Basin details regarding "drains to stream" button | Already required in the text, but should be emphasized on standards details as well | Chapter 5 |
| 2014-11 | Revisions to Drawing 5-11 | Add needed clarification on drawing | 5-11 - Post Construction Soil Quality and Depth |
| 2014-12 | Insert "the most current version of the" before Water System Plan and remove date | Clarity | 6.010/6.030 |
| 2014-13 | Make consistent the toning wire installation requirements for mains and service lines; also for conduit for street lights and fiber optics | Consistency in requirements | 6.030, 6.120, 7B.030E, 7B.080, 7C.030; other |
| 2014-14 | Remove 2nd sentence in 1st paragraph of 6.040: "See Olympia Standard Plans (Chapter 6 Drawings)." | Removes redundant sentence. | 6.040 |

EDDS 2014 - SUMMARY OF PROPOSED CHANGES - as of April 7, 2014

| EDDS # | Requested Change | Why? | Location in EDDS |
|---------|--|---|-------------------------------|
| 2014-15 | Change wording in 6.060H to say "Fire hydrants shall be abandoned per 6.200". | Removes redundant requirement. | 6.060H |
| 2014-16 | Increase vertical clearance for water meters from 4-6" to 8" min. | AMR Project requires more clearance for water meters | Drawings 6-1A thru 6-7 |
| 2014-17 | Modify Standard Plan (Drawing) 6-27 - See Email (DB-11-8-13) | Clarify what we already have as a standard, based on how most of our existing groundwater monitoring wells have been installed. | Drawing 6-27 |
| 2014-18 | Move all of the force main section 7D.050 (and delete) to 7C.030. | Eliminates conflicting sections addressing force mains. | 7C.030, 7D.050 |
| 2014-19 | Change sewer flow meter location to "in the bypass pumping port vault". | To get more accurate flow readings; recommended by system manufacturer. | 7D030P |
| 2014-20 | Revise grinder pump ownership description in 2nd paragraph of 7F.010. | Removes conflicting statements to accurately characterize current requirements. | 7F.010 |
| 2014-21 | Revise grinder pump tank volume required to be used in 3rd paragraph of 7F.020. | Reflects standard available pump/storage chamber sizes available from manufacturer. | 7F.020 |
| 2014-22 | Drawing 7-8A is listed in 7C.050 and List of Drawings, but is missing from drawings. | Adding drawing that was inadvertently omitted from 2013 version of EDDS. | Chapter 7 |
| 2014-23 | Replace Air Release model number ARB15 with new model number AR21 | Existing model number tends to leak | drawing 7-8 |
| 2014-24 | Remove phrase "by 2013" in 8.010. | Phrase no longer relevant. | 8.010 |
| 2014-25 | Insert "roll-off" in several places in section 8.020 and 8.05 | For clarity | 8.020, 8.035 |
| 2014-26 | Revise description of Drop Boxes/Compactors | For clarity | 8.031C |
| 2014-27 | Revise 8.033 Site Enclosure section | For clarity | 8.033 |
| 2014-28 | Add "container size and" to note at bottom of 8.035.4 | For clarity | 8.035 |
| 2014-29 | Drawing 8-4B is listed in the text, but not in the drawings. | Adding drawing that was inadvertently omitted from 2013 version of EDDS. | Chapter 8 |
| 2014-30 | Drawing 10-12A is listed in the drawings index, but not in the text - please correct | For clarity | Drawing Appendix - Chapter 10 |
| 2014-31 | Update text/standard drawing references per Code Publishing | For consistency with Code Publishing format | All |